2025-04-07 TBT Snow is Melting Site Cleanup & Spring Safety

2025-04-07 TBT Snow is Melting: Site Clean-Up & Spring Safety

With the snow melting across our sites, it’s time to stay alert and proactive about seasonal cleanup and safety. As we transition into spring, a few key hazards and tasks need our attention.

□□ Clean-Up Priorities:

- Clear debris, trash, and scrap that’s been uncovered by melting snow.
- Inspect walkways and jobsite areas for tripping hazards or pooled water.
- Drain or redirect standing water to prevent mud pits and erosion.
- Remove remaining snow piles near walkways, entrances, or equipment paths.

⚠ Watch Out For:

- Hidden objects in snowbanks – nails, stakes, rebar, etc.
- Slick spots from overnight freeze-thaw cycles.
- Soft or muddy ground creating unstable footing.
- Clogged or frozen drains causing water build-up.
- Exposed sharp or rusty materials creating injury risk.

□□ Safety Reminders:

- Wear proper PPE – waterproof boots, gloves, and hi-vis gear.
- Use cones or caution tape to mark hazards.

- Don’t lift heavy, wet items alone – team lift or use equipment.
- Be cautious when operating or parking machinery on soft ground.

Let’s keep our sites safe, clean, and productive.
If you see a hazard or need support with cleanup, speak up or reach out to your supervisor.
Teamwork now helps us avoid accidents later.

By Clicking "Mark as Read" - you are acknowledging you have read this entire (opened appropriate attachments) ToolBox Talk and understand this is company policy and will abide by regulations outlined in this safety policy. Please complete your acknowledgement within 24 hours of release. If you are receiving this notice, you are REQUIRED to read this content.

Revision #1
Created 2025-04-11 19:27:44 UTC by Dale Bergman
Updated 2025-04-11 19:28:20 UTC by Dale Bergman